

Operator Rains & Williamson Oil Co., Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

Well No. #1 Lease Name Bachman

S 6 T 13SR 13 R W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 2810-2843, 30 (30) 30 (30). Weak blow died 7 min. in 2nd opening. Rec. 70' mud w/oil specks on top of tool. FP's 39-48, 58-58. IBHP 1011, FBHP 982. Temp. 93°.			<u>E. Log Tops</u> Topeka Heebner Lansing BKC Cherty Cong. ERO Arb. LTD	2636 (-891) 2866 (-1121) 2920 (-1175) 3193 (-1448) 3263 (-1518) 3293 (-1548) 3359 (-1614)
DST #2 - 2911-2959, 30 (30) 60 (30). Rec. 40' muddy oil, 120' slightly oil cut mud, 180' water cut mud w/oil specks. FP's 65-98, 120-175. IBHP 1089, FBHP 1068. Temp. 101°.				
DST #3 - 2961-2988, 30 (30) 30 (30). Weak blow - 20 min. Rec. 90' water cut mud & oil on top of tool. FP's 54-65, 87-87. IBHP 1110, FBHP 1110. Temp. 104°.				
DST #4 - 3083-3120, 30 (30) 30 (30). Weak blow - died 17 min. Rec. 40' mud w/specks oil. FP's 54-54, 65-65. IBHP 786, FBHP 689. Temp. 102°.				
DST #5 - 3132-3165, 30 (30) 30 (30). Very weak blow - died 23 min. Rec. 40' mud. FP's 65-65, 65-65. IBHP 76, FBHP 65.				
DST #6 - 3296-3310, 30 (30) 60 (30). Strong blow. Rec. 320' muddy water, 2200' saltwater. FP's 274-721, 906-1121. IBHP 1131, FBHP 1131. Temp. 104°.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Wilson Rains Signature
 Wilson Rains President
 Title
 11-14-78 Date
 Date