

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Plotted Texas CO.


Company - M. B. ARMER ET AL
Farm - Olson No. 1.

SEC. 27 T. 13 R. 13 W
C NE NE

Total Depth. 3422'
Comm. 1-11-44
Shot or Treated.
Contractor.
Issued. 3-18-44

Comp. 2-21-44

County. Russell
KANSAS



CASING:

12 1/2" 485' 7" 2938' UR 3093'
10" 795' 5" 3385'
8" 2435'

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

cellar	8	shale	2615
rock	12	lime	2630
clay yellow	15	shale	2750
shale blue	40	lime	2845
shale	200	shale	2850
lime sdy	235	lime	2995
shale	250	shale blue	3005
shale red	275	shale sdy	3010
shale	385	lime	3030
shale blue	425	shale red & blue	3035
shale	470	shale	3060
sand	475	lime K.C.	3072
shale red	787	shale	3080
lime	830	lime	3135
shale red	980	shale	3140
shale blue	1030	lime	3210
shale red	1075	lime sdy	3230
shale blue	1105	lime	3240
shale	1200	shale	3245
salt	1445	lime	3285
shale	1475	shale	3290
lime	1485	lime	3317
shale	1500	shale	3325
lime brkn	1580	lime	3345
red rock	1585	shale	3350
lime	1590	lime	3360
shale & shells	1650	conglomerate	3385
redrock	1655	lime	3389
shale & shells	1705	conglomerate	3397
red rock	1720	sand brkn	3405
lime	1875	lime	3422
shale	1900	Total Depth.	
lime	1925		
shale	1930		
lime sdy	1970		
lime	2000	Water Record:	
red rock	2005	Water H. F.	220
lime	2075	"	2430-40
red rock	2085	"	2475-80
lime	2115	"	3080-85
shale	2125	"	3420-22
lime	2130		
shale cave	2140	sh gas	2425-30
lime	2150		
red rock	2160	Tops:	
shale	2200	Topeka	2750
lime	2225	K. C.	3060
shale	2240	Conglomerate	3360
shale & shells	2305	Arbuckle	3407
caving	2305-2470		
shale	2470		
lime brkn	2480		
lime	2490		
shale	2500		
lime	2505		
shale sdy	2530		
shale cave	2570		
shale	2585		
lime	2595		