

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

API No. 15 — 167 — 21696
County Number

Operator

Rains & Williamson Oil Co., Inc.

Address

435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Well No.

#1

Lease Name

Foster

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Rains & Williamson Oil Co., Inc.

Geologist

Dave Callewaert

Spud Date

5-13-81

Total Depth

3283'

P.B.T.D.

Date Completed

5-22-81


Oil Purchaser

S. 8 T. 13S R. 14 ^{XX}W

Loc. SW NE NE

County Russell

640 Acres



Locate well correctly

Elev.: Gr. 1803

DF KB 1808

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	20#	250'	60/40 poz.	160 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rains & Williamson Oil Co., Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. #1	Lease Name Foster		
S <u>8</u> T <u>13</u> SR <u>14</u> ^{EX} _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
<u>DST #1 - 2994-3034. Rec. 20' mud.</u> <u>FP's 21-21, 31-31. IBHP 624, FBHP 582.</u> <u>DST #2 - 3044-3086, 30 (30) 60 (30).</u> <u>Rec. 220' SI.OCMW. FP's 31-42, 73-104.</u> <u>IBHP 634, FBHP 624.</u> <u>DST #3 - 3131-3176, 30 (30) 60 (30).</u> <u>Rec. 40' SI.OCM. FP's 21-21, 31-31.</u> <u>IBHP 965, FBHP 882.</u> <u>DST #4 - 3229-3261, 30 (30) 30 (30).</u> <u>Rec. 15' mud. FP's 21-21, 22-21.</u> <u>IBHP 33, FBHP 21.</u> <u>DST #5 - 3229-3271, 30 (30) 30 (30).</u> <u>Rec. 40' mud. FP's 42-52, 42-52.</u> <u>IBHP 239, FBHP 177.</u> <u>DST #6 - 3229-3275, 30 (30) 30 (15).</u> <u>Rec. 45' MW. FP's 32-32. IBHP 924.</u>			<u>SAMPLE TOPS</u> Anhydrite 850 (+958) B/Anhydrite 885 (+923) Topeka 2711 (-903) Heebner 2933 (-1125) Lansing 3010 (-1180) BKC 3230 (-1422)
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Wilson Rains Signature _____ President _____ 6-1-81 _____ Date		