

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- B. W. SHINDHELM ET AL
Farm- Rogg No. 1

SEC. 7 T. 13 R. 11W
NW SE SW

Total Depth. 3254'
Comm. 1-6-56 Comp. 1-16-56
Shot or Treated.
Contractor. Mast Drlg. Co.
Issued. 4-7-56

County Russell
KANSAS

8" CASING:
200'

Elevation. 1798' KB

Production. Dry

Figures Indicate Bottom of Formations.

rock	65
shale & shells	440
shale	449
hard sand	459
shale & red bed	668
red bed	860
anhydrite	893
shale & shells	1365
shale & lime	1750
lime	1935
lime-sand-shale	2015
shale	2160
shale & lime	2260
shale	2639
shale & lime	2987
lime	3254
Total Depth	

Tops: KB	
Anhydrite	860
Topeka	2688
Hæbner	2915
Toronto	2936
Lansing	2968
Arbuckle	3240

DRILL STEM TESTS:

- #1 2964-77', open 45 mins., shut in 15 mins.
weak blow for 10 mins., rec. 04' mud. BHP 35#.
- #2 3005-18', open 45 mins., shut in 15 mins. Weak
blow for 18 mins. Rec. 14' slightly gas cut water
and mud. BHP 100#.
- #3 3242-54', open 1 hr., shut in 15 mins., fair blow
for 1 hr., rec. 170' muddy sulphur water. BHP 1005#.