


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- JAY-BEE OIL CO.  
 Farm- Rogg No. 2

SEC. 7 T. 13 R. 14W  
 NW NE SE

Total Depth. 3100'  
 Perm. 1-30-66 Comp. 2-9-66  
 Shot or Treated.  
 Contractor. Gabbert-Jones, Inc.  
 Issued. 5-7-66

County Russell  
 KANSAS



Elevation. 1658' D.F.

Production. 57 BOPD & 35% wtr.

**CASING:**

8 5/8" 264' w/210 sx em.  
 5 1/2" 3090' w/100 sx cem.

Figures indicate Bottom of Formations.

red rock, shale	0-200
shale, lime	264
sand, shale	355
shale, red bed	705
Anhydrite	740
shale, shells	1365
shale, lime	1670
lime	2050
lime, shale	2645
lime	3100
Total Depth	

**TOPS: ELECTRIC**

Heebner	2758
Toronto	2778
Douglas	2791
Lansing	2811
Warbuckle	3086

**TOPS: SCOUT**

* Anhydrite	705
* Topeka	2530
*Sample tops.	

DST #1-2812-2825. Op. 1 hr.  
 with a weak blow for 15".  
 Rec. 20' of oil cut mud with  
 a show of free oil on the  
 tool.

IBHP	372#/30'	FBHP	44#/30"
IFP	14#	FFP	22#

DST #2-2838-2851..Op. 1 hr. with  
 a strong blow. Rec. 100' slightly  
 OCM and 330' water.

IBHP	515#/30"	FBHP	470#/30"
IFP	44#	FFP	218#

DST #3-2984-3005. Op. 1 hr. with a  
 weak blow. Rec. 60' muddy water.

IBHP	990#/30"	FBHP	817#/30"
IFP	29#	FFP	44#

DST #4-3038-3095. Op. 30". Weak blow  
 for 7". Rec. 15' OCM with a show or  
 free oil on tool.

IBHP	930#/30"	FBHP	854#/30"
IFP	14#	FFP	29#

DST #5-3090-3100. Op. 30". Weak blow  
 for 12". Rec. 25' slightly OCM.

IBHP	937#/30"	FBHP	817#/30"
IFP	22#	FFP	29#