


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DERBY OIL CO. ET AL
Farm - Rogg "A" No. 1

SEC. 7 T. 13 R. 14 W
NW SW SE

Total Depth. 3265'
Comm. 7-1-45 Comp. 7-30-45
Shot or Treated.
Contractor. Kiowa Drlg.Co.
Issued. 8-25-45

County. Russell
KANSAS



Elevation. 1792 ft

Production. Dry

CASING:

8 5/8" 407' Cem.
5 1/2" 3236' Cem.

Figures Indicate Bottom of Formations.

surface clay	0-260
sand, shale & shells	410
shale & shells	520
red bed	770
red bed & shale	835
lime	875
shale & shells	1280
salt	1470
lime & shale	1610
shells	1625
lime & shale	1900
lime	1980
shale & lime	2788
lime	2833
lime & shale	2950
K. C. lime	3035
lime	3078
lime & shale	3123
lime	3127
Arbuckle lime	3265
Total Depth.	

Tops;
Lansing 3006
Arbuckle 3232

Fair to good odor & sat. in Arb.
DP CO no show; shot 12 on btm,
then 12 up hole 4'; 500A 1200#
rec. 1 qt blk wtr. 2 hrs. -
would not take acid DD 3247' -
no fillup - DD 3254' swab 2 gal.
oil from 3250-52' & 4 gal. oil &
12 gal. wtr from 3252-54'; 500A
would not take - set 36 hrs.
Swbd 1.34 BO & 5 BW DD 3265' TD
test 65 gals. wtr. per hr. D&A