


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RUDY HERMAN
Farm- Mayers No. 1

SEC. 15 T. 13 R. 14W
NW NW SW

Total Depth. 3290'
Comm. 5-24-62 Comp. 6-3-62
Shot or Treated.
Contractor. Sholom Drilling Co., Inc.
Issued. 1-19-63

County Russell
KANSAS



Elevation. ~~3290'~~
1805 KB

Production. 27 BOPD & 100 BW

CASING:

8 5/8" 289' cem w/190 sx.
5 1/2" 3257' cem w/175 sx.

Figures Indicate Bottom of Formations.

post rock	74
shale & clay	225
sand	245
shale	274
plug & cement	289
shale & sand	335
hard sand & pyrite	371
sand & shale	485
red bed	829
anhydrite	867
shale & shells	1300
lime & shale	2717
lime	3035
lime & chert	3060
lime	3265
arbuckle dolomite	3285 RTD
arbuckle dolomite ?	3290
Total Depth	

TOPS: SCOUT

Anhydrite	829
Grand Haven	2348
Tarkio Sand	2370
Tarkio Lime	2418
Topeka	2683
Heebner	2910
Toronto	2930
Lansing	2967
Base Kansas City	3202
Arbuckle	3249

DST #1 2861-2880' Rec. 20' mud.

DST #2 2938-2982' Rec. 460' gas in
drill pipe, 80' O&GCM.

DST #3 2975-2997' Rec. 100' gas & 240'
HO&GCM & 120' O&GCW & 120' SO&GCW & 120'
Water.

DST #4 3000-3012' Rec. 600' gas & 60'
HO&GCM & 60' Muddy oil.

DST #5 3036-3060' Rec. 1410' salt water.

DST #6 3118-3165' Rec. 70' gas & 100' water.