

INDIAN TERRITORY ILLUMINATING OIL CO.
Driscoll No. 1.

SEC. 21 T. 13 R. 14W.
NEC SW


OCT 20 1934

County. Russell.

Total Depth. 3383
Comm. 8-13-34 Comp. 10-5-34
Shot or Treated.
Contractor. Advance Drilling Co.
Issued. 10-20-34.

CASING.

20" 31' 8 1/4" 3004'
15 1/2" 363' 65/8" 3205'
12 1/2" 866 1/2 UR 887 53/16" 91' of liner 3291.
10" 2462
Lowered 2472'



Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

cellar	10	shale	1810	shale	2605
shale light	18	lime	1815	lime white	2612
shale blue	160	shale	1820	shale	2620
sdv shale light	165	lime	1910	lime	2628
1/2 BW 160-65		shale	1920	shale	2655
shale blue	210	hole caving some.		slate blue	2678
shale	250	lime	1975	lime	2700
red rock	260	shale	1980	shale hole cav.	2705
shale	270	lime	1985	lime	2727
red rock	300	red rock	2005	shale	2742
shale blue	315	lime	2035	lime	2758
sand	375	shale	2045	shale	2763
HFW 315-340		hole caving.		lime	2974
iron and sand	385	lime	2060	hole caving 2840-2905	
sand hard	394	shale	2065	shale	2978
iron and sand	400	lime	2085	lime	2991
shale blue	415	shale	2090	shale green	2994
sand	505	red rock	2095	lime	3006
shale blue	520	lime white	2152	3006 equals 3004 SLM	
red rock	540	shale light	2160	lime 3004-	3007
sand	565	lime	2170	red rock	3011
red rock	760	shale	2175	shale blue	3028
sand red	775	lime	2180	lime	3042
corrected C.M. 836 equals 830		shale	2185	shale	3045
red rock	870	red rock	2195	lime broken	3060
865 equals 866 1/2 SLM		hole caving.		how oil 3060	
gypsum	875	lime	2210	lime	3110
anhydrite	912	shale blue	2225	water sand	3120
water broke in at 875		shale	2235	3 BW 3110-20	
red rock	1060	hole caving.		lime	3205
hole caving some started to		lime	2260	cable Meas. SLM 3205=	
dump wtr 1040		shale	2278	3206'	
shale blue	1085	lime	2292	shale	3207
red rock	1145	shale	2320	lime	3235
hole caving 1100		hole caving badly		shale	3247
shale blue	1165	lime	2325	lime	3266
red rock	1180	shale	2355	shale	3270
shale blue	1260	fighting cave		lime	3272
salt	1555	lime	2370	shale	3275
lime	1580	shale blue	2380	lime	3284
shale	1585	shale grey	2405	shale	3291
lime	1595	shale	2462	lime	3295
shale	1600	shale	2471	red rock	3297
lime	1625	lime	2487	lime red	3299
shale	1630	2475 equals 2478 SLM		lime	3305
hole caving some dumping wtr		shale	2530	shale	3306
lime	1646	lime	2535	lime	3308
red rock	1654	shale	2539	conglomerate	3340
lime	1662	lime	2548	congl. all colors	3356
shale blue	1670	shale	2555	shale	3360
lime	1705	lime	2560	lime	3381
shale	1715	shale	2565	hole bailed dry at 3374	
lime	1755	lime	2575	water sand	3383
red rock	1785	shale	2580	water 3381-83. filled	
lime	1805	lime	2595	up 1200' could not	
				lower by steady bailing.	
				TD.	