

Plotted Texas CO.

County. Russell,

Total Depth. 3279

Comm. 1-17-36

Comp. 3-17-36.

Hot or Treated

Contractor.

Issued. 5-2-36.

MAY 2 1936

CASING.

15 1/2" 359'6" 65/8" 3313'10"
12 1/2" 862'2"
10" 2475'3" 3299'4" 3" tubing.
8 1/4" 3049'5"

Elevation.

Production Pot. 1009 B.

Figures Indicate Bottom of Formations.

clay yellow	35	lime	1875	lime	2860
shale dark	85	shale light	1890	shale	2865
shale blue	190	red rock soft	1895	lime	2870
shale grey	220	lime	1920	shale	2875
red rock	235	shale	1930	lime	2940
shale blue	245	lime	1950	shale white soft	2945
red rock	305	shale	1960	lime grey soft	2950
shale grey	315	red rock	1965	lime wh soft	2960
HFW 315-20		lime	1980	lime grey hard	2970
sand	365	shale	1985	shale light soft	2975
iron	380	shale andshells	2000	red rock	2980
Bad hole 377-80		lime	2015	shale	2995
sand	385	red rock	2025	lime grey hard	3010
iron broken	390	lime light hard	2075	shale white soft	3015
shale dark	395	shale	2085	lime white hard	3020
iron	403	shale andshells	2095	water from 3020-25	
sand soft	415	red rock	2108	sdv lime	3035
shale grey soft	445	lime	2160	lime light hard	3050
shale grey & blue	485	shale	2165	lime light med	3073
shale blue soft	505	red rock	2175	shale	3075
red rock	525	lime grey hard	2185	sdv lime light hard	3095
shale blue	535	red rock	2190	lime light hard	3135
red rock	852	lime grey	2200	shale dark soft	3140
anhydrite	892	shale grey	2205	shale light soft	3145
red rock	1035	lime grey hard	2260	cavo from 3135-45	
shale blue soft	1080	shale	2265	lime	3205
red rock soft	1130	lime	2285	shale dark soft	3223
shale	1150	shale dark soft	2300	lime	3230
red rock	1160	lime shells & shale	2310	shale grey	3234
shale blue soft	1180	shale and shells	2335	lime light hard	3253
shale salt shells	1205	lime light hard	2365	shale	3260
shale	1235	shale dark soft	2380	shale green & shells	3271
salt	1510	lime sdv	2385	gypsum	3272
shale grey soft	1518	red rock	2395	lime brown hard	3276
lime grey hard	1533	shale dark soft	2450	sdv lime	3279
shale light soft	1538	lime	2460	hole filling up with	
lime	1550	shale light soft	2463	oil 3278	
shale	1560	lime brown hard	2470	Total Depth.	
lime	1565	shale grey soft	2475		
shale and lime shells	1580	shale	2512		
lime	1590	lime	2517		
shale	1595	shale	2520		
lime grey hard	1600	lime	2525		
shale blue soft	1605	shale	2535		
lime grey hard	1620	lime grey hard	2540		
red rock & shale	1635	shale dark soft	2545		
shale and shells	1645	lime grey hard	2565		
lime broken	1655	shale grey soft	2580		
lime hard	1675	lime grey hard	2590		
shale and shells	1692	shale blue soft	2610		
lime broken	1705	lime grey hard	2615		
shale blue	1710	shale light soft	2655		
lime	1730	lime	2670		
red rock & shells	1745	shale and shells	2680		
red rock soft	1755	lime	2690		
lime grey hard	1785	shale blue soft	2700		
sdv shale	1820	lime grey hard	2705		
lime	1840	shale dark soft	2720		
shale	1845	show oil 2720-30			