

PL

KANSAS

State Geological Survey


WICHITA, BRANCH

S. 22 T. 13 R. 14 ^KW

Loc. C W2 SW SW

County Russell

640 Acres
N



Elev.: Gr. 1840

DF 1842 KB 1845

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 167 — 21,487
County Number

Operator

Barton Oil Co.

Address

129 Elm Russell, Kansas 67665

Well No.

#1

Lease Name

Steinle

Footage Location

660 feet from (S) line

330 feet from (W) line

Principal Contractor

Emphasis Oil Co

Geologist

Jerry J. Knobel

Spud Date

7-7-80

Date Completed

7-19-80

Total Depth

3469

P.B.T.D.

3220

Directional Deviation

Oil and/or Gas Purchaser

N.C. R.A.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		264	Pes mix	160	2% gel 18 3% c.s.
Production	7 7/8"	4 1/2"	10.5	3330	common	100	10% salt.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jet	3186-88
			4	Jet	3272-74

Size	Setting depth	Packer set at
2"	3215	NONE

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gallon 28% — 5000 gallon 28%	3186-88

INITIAL PRODUCTION

Date of first production 8-1-80		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil 10 bbls.	Gas NONE MCF	Water 50 bbls.	Gas-oil ratio 20% CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval(s) 3186-3188	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Barton Oil Co.

oil

Well No.

1

Lease Name

Steinle

S T R E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

854

890

Anhydrite

854(+991)

Howard

2647(-802)

Topeka

2711(-866)

Heedner

2938(-1093)

Toronto

2958(-1113)

W-K.C.

2996(-1151)

Base of K.C.

3252(-1407)

Arbuckle

3266(-1421)

R.T.D.

3469(-1624)

Open hole electric log run
by Great Guns & cased
hole log run by W.K. Wireline

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Athol C. Barton

Signature

operator

Title

12-1-80

Date