

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Union National Bank Bldg, Wichita, Kansas

Plotted

Plotted Texas CO.

SEC. 22 T. 13 R 14W
NWc SW

FEB 24 1934

TOM PALMER
Steinle No. 1

County. Russell

Total Depth, 3286
Comm. 12-10-33 Comp. 2-12-34
Shot or Treated.
Contractor.
Issued. 2-24-34

CASING

20" 38' 10" 2175'
15 1/2" 400' 8" 2510' UR 2775
12 1/2" 859' 6 5/8" 3276

Elevation.

Production, 1089B. 24 Hours.
Pot.

Figures Indicate Bottom of Formations.

cellar	12	shale	1970	shale blue	3045
clay	37	lime	2030	HFW	
slate	50	red rock	2035	lime sdy	3075
shale	160	lime	2050	water sand	3085
lime	170	red rock	2055	lime white	3138
shale	220	shale	2060	lime blk	3153
red rock	240	lime	2095	shale	3155
shale	255	red rock	2110	lime white	3175
red rock	265	lime	2115	sdv lime	3180
shale	305	shells and red rock	2140	lime	3190
sand	325	red rock	2170	shale	3193
shale	330	lime	2190	lime	3215
sand	375	shale	2225	shale CAVE	3225
Thin layers of pyrite below	375	lime	2235	lime	3234
sand	405	shale	2255	lime sdy	3236
Pyrite	415	lime	2265	showing of oil	3234
sand	430	shale	2335	lime	3263
mud	440	lime	2355	shale	3275
shale	480	shale	2375	lime	3286
sand white	490	lime	2385	T.D.	
shale	515	shale	2395		
sdv shale	550	lime	2400	Oil from 3283-3286	
red rock	850	shale	2450		
anhydrite	895	lime CAVE	2475		
red rock	1040	shale	2510		
shale	1090	lime	2525		
red rock	1135	shale	2540		
shale	1155	lime	2550		
red rock	1160	shale	2555		
shale	1270	lime	2560		
salt white	1495	shale	2570		
shale blue	1500	lime	2580		
salt	1530	shale	2590		
lime hard	1540	lime	2595		
shale and shells	1555	shale	2615		
shale	1565	lime	2620		
lime	1575	shale	2650		
shale	1585	lime	2670		
shell	1615	shale	2675		
shale	1620	lime	2705		
lime	1625	shale	2720		
red rock	1645	lime	2775		
lime	1678	lime grey	2795		
shale and red rock	1680	lime sdy	2810		
shale	1695	showing oil	2795		
lime	1735	lime white	2895		
red rock	1760	lime broken	2950		
lime	1800	shale	2955		
shale	1805	lime	2958		
lime	1880	shale	2965		
shale	1890	lime extra hard	2990		
red rock	1895	red rock and shale blue	3005		
lime	1920	lime	3010		
shale	1935	shale green	3013		
lime	1955	lime	3042		