


TOM PALMER
Killian No. 6

SEC. 27 T. 13 R. 14W.
SWc SE NW

APR 6 1935

Plotted Texas CO.
County. Russell.

Total Depth. 3293
Comm. 2-1-35 Comp. 3-17-35
Shot or Treated. 1000 gal acid.
Contractor. Tom Palmer.
Issued. 4-6-35.



CASING.

15 $\frac{1}{2}$ " 353'9" 8 $\frac{1}{4}$ " 2476'2"
12 $\frac{3}{8}$ " 567'5" 65/8" 3308'4"
10" 880'11". Ran 3271'7" 3" tubing.

Elevation.

Production. Pot. 528 B.

Figures Indicate Bottom of Formations

cellar soft	10	red rock soft	2170
post rock soft $\frac{1}{2}$ BWH 205	30	lime white hard	2195
shale soft dark -10	205	shale blk soft	2200
shale light	245	lime white hard	2250
shale red soft	265	shale soft	2275
shale grey soft	278	lime B. hard	2290
red rock soft	300	shale blue soft	2320 hole caving 2325
shale blue soft	320	lime white hard	2345
sand light soft	350	shale and shells	2355
iron hard	354	shale blue soft	2375
sand grey soft	364	lime hard	2390
iron hard	400	gas sand soft	2395
sand	401	shale blue soft	2430
shale	455	shale blk soft	2447
lime white hard	470	lime	2475
shale blue soft	480	shale blue soft	2505
lime white hard	485	lime hard	2525
shale blue soft	505	shale soft hole caving	2535
red rock soft	860	lime hard	2565
lime hard	865	shale light	2570
anhydrite	910	lime white hard	2580
red rock soft	1055	shale light soft	2600
shale light soft	1100	lime light hard	2610
red rock soft	1175	shale light soft	2655
shale blue soft	1285	lime blue hard	2670
red rock	1295	shale & shells blue sft	2690
salt	1485	shale light soft	2710
shale blue	1510	lime hard	2755
lime brown	1525	shale & shells	2760
shale blue	1530	shale blue soft	2765
lime	1535	lime white hard	2780
shells wh & shale sft	1590	shale white soft	2785
shale light soft	1610	lime hard	2795
lime light hard	1625	shale and shells	2805
shale light soft	1635	lime hard	2845
lime light hard	1640	shale soft	2850
red rock soft	1645	lime hard	2895
lime brown hard	1665	shale	2900
shale blue soft	1685	lime	2955
red rock soft	1690	shale white soft	2960
shale blue soft	1710	lime white hard	2970
lime white hard	1730	shale	2975
shale white soft	1735	red rock	2985
red rock soft	1755	shale	2995
lime white hard	1780	lime hard	3176 3BWH 3040 sh oil.
shale light hard	1805	red rock	3181 3 BWPB 3040 more oil.
lime light hard	1835	shale	3185 water fr 3080-3084
lime brown hard	1885	lime	3203 HFW 3165-70
red rock soft	1895	lime grey hard	3206
lime white hard	1920	shale	3225 2BWPB 3225 show oil.
shale white soft	1925	lime light hard	3239 hole caving very badly
lime white hard	1955	shale light soft	3250
shale soft	1970	lime light hard	3261
lime hard	1995	shale light soft	3264
shale light soft	2015	lime light hard	3274
lime hard	2025	shale	3279
red rock soft	2050	lime soft	3282
lime white hard	2080	lime hard	3293 Total Depth.
red rock soft	2095	oil from 3290-92.	
lime hard	2160		
red rock cave at 2100			