


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
Farm-Mohl No. 1

SEC. 27 T. 13 R. 14W
~~SE~~ SW NE
SW

Total Depth. 3277
Comm 12-19-52 Comp. 1-16-53
Shot or Treated. Acid 1500 gals.
Contractor. Shields Drilling Co., Inc.
Roused. 2-7-53

County Russell
KANSAS



CASING:
8 5/8 145' w/ 100 sx cement
5 1/2 3263.5' w/ 100 sx cement

Elevation. 1837 RB

Production. 50 BOPD, no water

Figures indicate Bottom of Formations.

surface clay & rock	95
shale & clay	145
shale & sand	210
shale	355
iron, shale & sand	380✓
iron & sand	475✓
iron & shale	490✓
shale & red bed	565
red rock	825
anhydrite lime	870
shale, shells & red rock	1125
shale & shells	1185
shale, shells & salt	1400
broken lime & shale	1585
lime	1650
lime & shale	1725
broken lime & shale	1780
lime & shale	2030
broken lime & shale	2115
lime & shale	2245
brown lime & shale	2325
shale & lime streaks	2379
lime & shale	2835
lime	2880
lime & shale	2988
lime	3039
lime & shale	3242
conglomerate	3259
Arbuckle lime	3263
lime	3277
Total Depth	

Tops:	
Tarkio	2379
Topeka	2704
Heebner	2932
Toronto	2950
Lansing KC	2989
Arbuckle	3262

SLM 3263 = 3266

Notes: D.P. CO to 3266 1 BOPH/5 hrs. Acid
500. No increse. Acid 500 2 BOPH/4 hrs.
D.D. 3270. SS0 D.D. 3277 GSO Acid 500
Electric Pilot. Swb 14 BOPH/9 hrs No wtr.
POP

RTD 3266
CTD 3277