


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
Farm- Mohl-Shaffer Unit No. 2

SEC. 27 T. 13 R. 14W
SE SW NE
Lot 7, Block 69

Total Depth. 3305-
Comm. 4-24-53 Comp. 5-4-53
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 5-30-53

County Russell
KANSAS



CASING:
8 5/8" 145' cem w/ 65 sx
5 9/16" 3266' cem w/100 sx

Elevation. 1839 RB
1837(2).
Production. dry

Figures Indicate Bottom of Formations.

| | |
|------------------------|------|
| rock | 30 |
| clay, shale | 155 |
| shale | 350 |
| shale, iron | 390 |
| shale | 460 |
| shale, shells | 485 |
| red bed, shale | 860 |
| anhydrite | 890 |
| shale, red bed | 920 |
| shale, shells | 1285 |
| shale, shells, salt | 1500 |
| lime broken | 1585 |
| lime, shale | 1810 |
| lime | 1870 |
| lime, shale | 2060 |
| lime brkn, shale | 2225 |
| lime, shale | 2570 |
| shale | 2640 |
| lime, shale | 3011 |
| lime | 3162 |
| lime, shale | 3262 |
| shale, congl. | 3265 |
| dolomite, wht, coarse | |
| xyn, sandy | 3270 |
| shale, green, pyritic, | |
| sandy | 3272 |
| dolomite, very cherty, | |
| pyrite, tripolitic | |
| cherts | 3300 |
| dolomite, gry, sulfur | |
| water | 3305 |
| Total Depth | |

| | |
|---------------------|------|
| Tops: | |
| Tarkio sand | 2379 |
| Topeka | 2704 |
| Heebner | 2930 |
| Toronto | 2949 |
| Lansing-Kansas City | 2989 |
| Conglomerate | 3257 |
| Arbuckle | 3265 |

RTD 3266

Show gas 2380-90

Note: DP:NS:DD, 3305, 1/3 B.
sulphur WPH: PB 3200, perf.
3178-80, 3167-72, 3153-67, SSO,
Acid 2000, swb 3/4 BFPH, 50% oil;
PB 3050, perf. 3030-38, 3020-23,
3013-3017, Acid 1000, Swb 5 BFPH,
10% oil.