


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KIM OIL COMPANY
Farm- Ehrlich No. 2

SEC. 28 T. 13 R. 14W
SW NW SE

Total Depth. 3276'
Comm. 5-25-55 Comp. 6-24-55
Shot or Treated.
Contractor.
Issued. 5-4-57

County Russell
KANSAS



Elevation. 1861' DP

Production. 25 Bbls

Figures indicate Bottom of Formations.

CASING:

8 5/8" @220' w/125 sx cem.
5 1/2" @3274' w/75 sx cem.

NO LOG AVAILABLE

All tops were measured from the rotary drive bushing at an elevation of 1863' above sea level.

TOPS

Heebner 2956
Lansing/Kansas City 3011
Arbuckle 3272

Markio 2395-2445' Samples caught through the Tarkio section of this well, show a well developed sand.

Drill breaks had a slight odor, but very poor porosity in the samples.

Topeka 2735-70'
Dodge 2969-88'
3063-70; 3075-81; 3082-88;
3082-89; 3092-3108;
3168-76 Lansing/Kansas City

Arbuckle 3272-75 medium crystalline, sand studded dolomite. It had free oil and odor infair to good porosity. There was some tight fine crystalline dolomite.