


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KIM OIL CO., INC.
 Farm- Atherton East No. 10

SEC. 30 T. 13 R. 14W
 SW SW SE

Total Depth. 3336'
 Comm. 9-21-57 Comp. 10-25-57
 Shot or Treated.
 Contractor. Shields Drlg. Co.
 Issued. 3-22-58

County Russell
 KANSAS



Elevation. 1886 RB

Production. 25 BOPD

CASING:

8 5/8" 932' w/425 sx cem.
 5 1/2" 3334 1/2' w/100 sx cem.

NO LOG AVAILABLE.

Figures indicate Bottom of Formations.

- 2768-81 Topeka Fine xylm limestone with free oil, saturation and odor.
- 2941-65 Topeka fossiliferous limestone with some good inter fossil porosity, free oil and odor.
- 3045-61 Lansing Fine xylm and fossiliferous limestone with free oil, good odor and a trace of fair porosity.
- 3064-76 Lansing Fair porosity oolitic, oolitic and sucrosic fine xylm limestone with free oil and odor
- 3083-94 Lansing Odor and free oil in good porosity oolitic and oolitic limestone.
- 3117-24 Lansing. brown fossiliferous limestone with free oil in fair inter fossil porosity.
- 3221-27 Lansing fair fossiliferous porosity with free oil and odor.
- 3312-32 Conglomerate. Oolitic chert, chert and devitrified chert. Fine xylm and fossiliferous limestone, with spotted staining and free oil
- 3332-35 Arbuckle. Coarse xylm dolomite with free oil and good inter-crystal porosity.

RTD 3335

Total Depth 3336

TOPS:

Topeka	2768
Heebner	2993
Dodge	3011
Lansing-Kansas City	3045
Arbuckle	3332

TOPS ; Scout

Anhydrite	915
Conglomerate	3212