


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- ICER ADDIS
 Farm- Brown No. 1

SEC. 31 T. 13 R. 14W
 NW NW SE

Total Depth. 3303'
 Comm. 8-5-57 Comp. 8-16-57
 Shot or Treated.
 Contractor. Duke Drlg.
 Issued. 6-14-58

County Russell
 KANSAS



CASING:
 8 5/8" 222' cem.
 5 1/2" 3295½' cem.

Elevation. 1870' KB

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface clay & post	
rock	80
sand	95
shale & sand streak	180
sand	215
blue shale	240
sand	250
shale	325
sand	340
shale & sand streak	350
shale	390
sand	450
shale	505
sand	526
shale	550
sand	580
shale	587
red bed	900
Anhydrite	940
shale & red bed	1125
shale & shells	1285
salt & shale	1400
shale & shells	1650
lime & shale	1925
broken lime	2040
lime & shale	2730
lime	2975
Heebner	3000
lime	3026
Lansing	3078
lime	3294
Arbuckle	3297 RTD
lime	3303
Total Depth	

TOPS:

Anhydrite	900
Topeka	2747
Heebner	2975
Toronto	2994
Lansing	3206
Base Kansas City	3261
Arbuckle	3294