

Plotted
 Texas Co.

SHELL PETRO. CORP.,
 S. Brown No. 1

SEC 31 T. 13 R. 14W.
 NEc SE
 330' fr NL 330' fr E.L. SE $\frac{1}{2}$

Total Depth. 3313.
 Comm. 5-1-36 Comp. 6-25-36
 Shot or Treated.
 Contractor. Thayer Drfg Co.
 Issued. 7-18-36

County. Russell.

JUL 18 1936



CASING.

16" 304' 85/8" 2354' Elevation.
 103/4" 923' 7" 3040' UR 3250' UR 3302

Production. Pot. 536 B.
 520 BW 24 Hr.s

Figures Indicate Bottom of Formations.

cellar	16	shale blue	1090		
surface yellow	45	shale brown	1100	shalo	2560
shale blue	90	red rock Hole cav.	1170	lime	2590
mud blue	145	rod rock	1195	shalo	2600
shale blue	195	shale blue	1250	lime	2610
sand white water 200'	205	salt	1290	shale	2625
sand	220	salt	1545	lime	2640
shale and shells pink	230	shale	1560	shale	2700
shale blue	250	lime white	1575	shalo	2720
shale red and white	265	shalo light	1590	lime	2735
shale white	275	lime	1615	carrying 4 BWPHR	
sand HFV	290	shale	1625	shale	2747
myd clay	304	lime and shale	1670	lime	2751
mud grey	305	shale	1675	shale	2758
shale light	315	lime	1680	lime	2770
shale dark HFV	345	shalo	1690	Trace oil 2747-51. no	
sand	355	lime and shale	1730	fill up. SLM 2765 No Corr.	
shale	365	shale brown	1735	shale Hole cav.	2780
salt	385	shale blue	1745	lime	2795
Skidded Rig.		lime	1775	lime	2845
cellar	10	shale sdy	1790	shalo	2852
clay yellow	45	shale brown	1805	lime	2980
shale blue	65	broken lime	1815	hole caving 1BW 2950.	
mud blue	105	lime	1825	shalo	2985
shale light	115	shale and lime	1840	lime	2995
shale blue	195	lime	1855	shalo	3000
sand	210	shalo	1865	lime	3015
sdv shale	225	lime	1890	hole caving bad.	
shale dark	245	shale light	1895	rod rock	3020
shale white	255	lime	1925	lime	3021
shale red	275	shale light	1935	shale blue	3030
sand	295	rod rock	1950	lime SLM 3040 No corr.	
100' water 295		lime	1975	Rainbow show oil 3110	
shale white	305	shale blue	1985	bailing test at 3110.	
shale light	315	lime	2000	bailed hole dry.	
shale blue	330	shalo	2020	recovered no water and	
shale blue	335	lime	2065	small scum oil.	
sand	370	shale brown	2075	1 1/2 BWPHR 3135-40.	
pyrite	380	lime white	2090	trace oil with water.	
sand and iron	395	sdv shalo	2110	preparing to UR 7" casin.	
Hold bad at 388.		lime white	2115	lime	3170
sand and iron	418	lime	2130	shalo	3173
shale blue	455	rod rock	2150	limb	3203
shale blue and muddy	490	lime	2200	3203 equals 3205 SLC	
shale blue	525	shalo	2230	show oil 3200-05	
sand white	530	lime	2275	lime	3212
shale blue	535	shalo	2280	show oil 3200-05	
sand pink	550	lime	2290	1 1/2 BOPH 3209	
rod rock	600	shalo	2305	no increawo oil 3216.	
shale blue	615	shalo	2315	shalo	3216
rod rock	745	lime broken	2325	lime	3236
rod rock and blue shale	785	shale light	2348	shalo	3240
rod rock	830	shale light	2348		
hole filling with water slowly		shalo	2354	lime	3260
from 336' on. small increases		shale blue	2385	shalo	3263
from 335-795. 700' water in		lime	2410	lime	3270
hole 795		shalo	2425	conglomerate	3275
rod rock	920	lime	2430	lime	3283
anhydrite and lime	924	shalo	2505	conglomerate	3301
anhydrite and lime	940	lime	2535	dolomite	3302
anhydrite	945	shalo	2550	OVER	
rod rock	1080	3 BWPHR 2505'			

Shell Petroleum Corp.
31-13-14W.

dolomite grey med hard some pale
green shale 3307

dolomite grey med hard coarsely
crystalline trace pale green shale
in partings 3309

Rainbow show oil in bailer.

Top Pay at 3309.

dolomite buff grey med soft
coarsely crystalline. 3311

dolomite buff grey very soft
very porous 3313

Plugged back 3313-3308 with sand and
oakum.

Total Depth.