


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **KIM OIL CO.**
 Farm- **Brown** No. **7**

SEC. **31** T. **13** R. **14W**
 SE SW NE

Total Depth. **3327'**
 Comm. **4-9-58** Comp. **4-21-58**
 Shot or Treated.
 Contractor. **Triangle Drlg.**
 Issued. **8-9-58**

County **Russell**
KANSAS



Elevation. **1873' KB**

Production. **25 BOPD**

CASING:

8 5/8" 915' cem w/425 sx.
5 1/2" 3315' cem w/150 sx.

Figures indicate Bottom of Formations.

surface clay & post rock	70
shale & clay	110
shale & shells	120
sand & shale	150
shale & shells	388
hard sandstone & shale stks	394
hard sandstone & pyrite	410
sandstone & shale	540
red bed	911
Anhydrite	947
shale & shells	1275
salt & shale	1375
shale & shells	1565
limestone & shale	1890
limestone	2000
broken limestone	2020
limestone & shale	2780
limestone	3314
Dolomite	3317 RTD
lime	3327
Total Depth	

TOPS:

Anhydrite	911
Heebner	2981
Toronto (scout)	3000
Lansing	3032
Conglomerate (scout)	3305
Arbuckle	3314