


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Boxberger "A" No. 2.

SEC. 32 T. 13 R. 14 W
N E SE NW
990' N & 330' W Center

Total Depth. 3309'
Comm. 1-13-44 Comp. 2-24-44
Shot or Treated. 1000 Gals. Acid 2-25-44
Contractor. Veeder Sup & Dev. Co.
Issued. 4-22-44

County. Russell
KANSAS



CASING:
8 5/8" 344' Cem.
4 1/2" 3298' Cem.

Elevation. _____

Production. Pmpd Pot. 178 B.
no wtr, 11 hrs

Figures indicate Bottom of Formations.

soil & clay	0-26
sand	125
shale & shells	200
sand & shale	305
shale & lime	344
shale & shells	400
pyrite & sand	415
sand	440
shale & shells	520
red bed	670
red bed, shale, shells	830
red bed & shale	891
anhydrite	948
red bed	987
shale	1018
red bed	1090
shale & shells	1317
salt, shale, shells	1500
shale & shells	1552
anhydrite	1595
lime	1660
anhydrite	1748
shale	1830
lime	1925
shale	1975
lime	2075
lime brkn	2140
lime & shale	2280
lime	2310
shale & shells	2360
lime & shale	2470
lime brkn	2900
lime	2910
chert & lime brkn	2965
lime	3303
3303 Rot. TD = 3298 SIM	
dolomite	3309
Total Depth.	

Corr. Top Arbuckle 3297
Penetration 12

Fillup: 150' Oil in 1 hr
300' Oil in 3 hrs
700' Oil in 5 hrs
1100' Oil in 9 1/2 hrs