

NSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS STATE SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK WICHITA, KANSAS
508 East Murdock

FEB 22 1968


COMPANY Clinton Oil Company WICHITA, KANSAS 67214
FARM Boxberger "A" NO. 2-D

SEC. 33 T. 13S. R. 14W
LOG. C NW NE SW

TOTAL DEPTH 3315'
COMM. November 23, 1968 COMP. December 3, 1968
SHOT OR TREATED
CONTRACTOR H-30, INC.
ISSUED

COUNTY Russell

KANSAS



CASING

20	10			
15	8-5/8"	248'	cemented w/160 sx cement	ELEVATION 1858 KB
12	6			
13	8-1/2"	3312'	cemented w/75 sx cement	PRODUCTION SWPW

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay	40
Clay, Post Rock, Streaks, Iron & Shale	250
Clay & Shale	390
Hard Sand & Iron	430
Shale & Streaks of Hard Sand	460
Red Bed & Shale	898
Anhydrite	934
Shale & Shells	1285
Shale	1297
Shale & Lime	1620
Lime & Shale	1950
Shale & Shells	2145
Lime, Shale & Shells	2325
Shale & Shells	2750
Lime & Shale	3058
Lime	3178
Lime & Shale	3225
Lime	3315
Rotary Total Depth	3315

SAMPLE TOPS

Base Anhydrite	934	+	924
Topeka	2741	-	833
Queen Hill	2888	-	1030
Heebner	2971	-	1113
Toronto	2990	-	1132
Douglas	3003	-	1145
Lansing	3024	-	1166
Base K.C.	3278	-	1420
Arbuckle	3307	-	1449
Rotary T.D.	3315	-	1457



I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS: