

KANSAS GEOLOGICAL SOCIETY
East Murdock
Wichita, Kansas
FEB 1 1963

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
505 EAST MURDOCK - WICHITA, KANSAS
Clinton Oil Company

33 133 14W
SEC. C SW SE NW
LOG.

COMPANY
FARM Bonberger

NO. 2-D


Russell

COUNTY

KANSAS

TOTAL DEPTH 3,308.5'
COMM. November 11, 1963
SHOT OR TREATED
CONTRACTOR H-30, INC.
ISSUED

COMP. November 22, 1963



CASING

20 12 5/8" 250' cemented w/160 sz cement
15 8
12 6 1/2" 3306' cemented w/150 sz cement
13 5

ELEVATION 1855 KB

ELEVATION

PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

Foot Rock, Iron & Shale 240
Red Bed & Shale 300
Hard Sand & Iron 410
Dry Hard Sand & Shale 430
Shale & Shells 808
Anhydrite 934
Shale & Shells 1000
Lime & Shale 1040
Shale & Shells 2720
Lime & Shale 3073
Lime 3163
Lime & Shale 3205
Lime 3222
Lime & Shale 3306
Lime 3308
Rotary Total Depth 3308 1/2

SAMPLE TOPS

Anhydrite	808	+	957
Anhydrite Base	934	+	981
Topoka	2735	-	880
Queen Hill	2806	-	1031
Hoobner	2968	-	1113
Toronto	2986	-	1131
Douglas	3003	-	1143
Lansing	3023	-	1168
Arbuckle	3304	-	1449
Rotary T.D.	3308 1/2	-	1453 1/2

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Rorer
ARLO B. RORER

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 26th day of November, 1963.