


Company - H. H. BLAIR  
 Farm - Driscoll No. 4

SEC. 34 T. 13 R. 14N  
 NE SE NE

Total Depth. 3276  
 Comm. 2-22-50 Comp. 5-3-50  
 Shot or Treated.  
 Contractor.  
 Issued. 10-21-50

County. Russell

KANSAS



Elevation. 1839 DF

Production. Est. 60 BO & NW

CASING:

8" 2500'  
 5" 3273'

Figures Indicate Bottom of Formations.

All measurements are taken from the derrick floor.

For log.	2692
shale, gray	2692-2705
limestone	2937
shale, soft blk	2939
limestone	2941
shale.	2960
limestone	2970
shale	2995
limestone	3019
shale	3027
limestone	3205
shale	3211
limestone	3237
shale	3243
limestone	3250
shale	3262
limestone	3272
dolomite	3276
Total depth	

Tops:

Heebner	2937
Dodge	2995
Base Oread	3019
Lansing	3019
Base Kansas City	3237
Arbucklo	3272

Remarks:

Sample log starts 2692; Possible pin-point porosity at top. Vugular porosity; very good stain 2812-20; Strks vugular porosity; good stain 2995-3000. Good porosity & fair to good stain 3027-3039. Vugular porosity, fair stain; depth questionable 3072-76. Fair porosity, possible trace stain at top 3076-3085. Some vug. por.; small stain 3155-3161. Probably porous; samples ground to fine to be certain; no stain, 3161-75. Good inter-oolitic porosity; trace stain 3180-82. Fair porosity; trace stain 3211-3218; No porosity 3218-25. Fair to good porosity with good stain 3272-76.