


KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CLARENCE WILHELM
FARM Deines NO. 3

SEC. 19 T. 13 R. 14W
LOC. NW NE NE

TOTAL DEPTH 3280'
COMM. 2-6-68 COMP. 2-14-68
SHOT OR TREATED
CONTRACTOR Shields Drlg.
ISSUED 3-23-68

COUNTY Russell



CASING
20 10
15 8 5/8" 873' cem w/ 425 sx
12 6
13 5

ELEVATION 1806' KB

PRODUCTION DRY/ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

Post rock, shale & sand	347'	TOPS: SMP	
Hard sand & pyrite	391'	Topeka	2700
Shale & redbed	865'	Heebner	2926
Anhydrite	895'	Toronto	2946
Shale & Shells	1,250'	Lansing	2981
Shale, shells & salt	1,530'	Arbuckle	3247
Shale & lime	1,850'		
Lime	2,025'		
Lime & shale	2,768'		
Lime	3,280' RTD		

NOTES

- DST #1 3,227' - 3,253' Tool open 1 hr w/ very weak blow for 10 min.
Recovered 5' mud. All pressures 0#
- DST #2 3,252' - 3,264' Tool open 1 hr w/ weak blow for 16 min.
Recovered 10' mud. All pressures 0#