


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - B & R DRILLING COMPANY
Farm - Gaynor No. 3

SEC. 19 T. 13 R. 14W
C S/2 N/2 NW/4

Total Depth. 3026
Comm. 11-10-48 Comp. 11-30-48
Shot or Treated.
Contractor.
Issued. 2-5-49

County. Russell
KANSAS



CASING:

8 5/8" 565' cem w/225 sx.
5 1/2" 2979' cem w/75 sx.

Elevation. 1813 Ind.

Production. 20 oil, and 150 wtr.

Figures Indicate Bottom of Formations.

surface clay and	
post rock	25
shale, pyrite	55
shale, shells	85
sand	90
shale, shells	140
sand	168
shale, shell and	
pyrite	255
red rock sdy	280
shale, shells	355
sand, iron, hrd	408
shale, shells	488
sand	501
shale, shells	505
sand, shale	525
shale, shells	565
red bed	873
anhydrite	913
shale, shells and	
red bed	1260
shale, salt	1450
shale, lime shells	1510
shale, shells, lime	1635
lime	1996
shale, lime	2704
lime	3026
total depth	

Tops:

Heebner shale	2926
Dodge lime	2944
Lansing K.C.	2978

Small oil show 2874-77&
2879-84&
2288-93&
2947-51&
2981