


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - EL DORADO REFG. & AYLWARD DRIG.
Farm - Boxberger No. 1

SEC. 32 T. 13 R. 14W
NE NE SW

Total Depth. 3296'
Comm. 1-24-49 Comp. 2-22-49 ✓
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 4-9-49

County. Russell
KANSAS



Elevation. 1862 feet.

Production. Est. 100 bbls.

CASING:

8-5/8" 179' Cem. W/150 Sx.
5-1/2" 3293' Cem. 3/75 Sx.

Figures Indicate Bottom of Formations.

surface	5
clay brwn	12
clay yellow & rock	38
shale blue & shells	190
sand	230
shale & shells	385
sand hrd & iron	395 ✓
pyrite of iron	422 ✓
shale blue	470
shale	525
shale & sand	660
shale	900
anhydrite	935
shale & shells	1385
salt & shale	1550
shale & shells	1850
lime sharp sdy	1870
lime & shale	1930
lime	2065
lime & shale	2170
shale & shells	2285
lime & shale	2330
shale	2381
lime & shale	2700
lime	2845
lime & shale	2900
lime	3035
shale & lime	3057
lime	3296
Total epth	

Tops:

Heebner	2972
Lansing	3023
Arbuckle	3292

Zone #1	3047-52
Zone #2	3068-70
Zone #3	3108-12
Zone #4	3120-35
Zone #5	3190-3215