


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ELDORADO REFINING AND AYLWARD DRILLING
Farm - Boxberger No. 2

SEC. 32 T. 13 R. 11W
NW NE SW

Total Depth. 3306
Comm. 3-31-49 Comp. 4-16-49
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 6-4-49

County. Russell
KANSAS



Elevation. 1866 Ind
Pot.
Production. 40 bbls.

CASING:

8" 165' Cem. w/115 sx.
5½" 3299½' cem w/75 sx.

Figures Indicate Bottom of Formations.

clay, gravel	30
sand, shale	165
shale, shells	310
sand	380
iron	430 ✓
sand, shale	545
sand, iron pyrite	570 ✓
sand	590
shale, shells	900
anhydrite	939
shale, shells	1260
salt, shale	1510
shale, shells	1565
shale, lime shells	1700
lime, shale	1820
shale, shells	1850
lime	1920
lime, shale	2030
lime	2075
lime, shale	2295
shale, shells	2490
lime	2500
shale	2580
lime	2600
lime, shale	2630
lime	2645
lime, shale	2727
lime	3008
shale	3027
lime	3155
lime, hrd	3195
lime	3306
Total Depth	

Tops:

Heebner shale	2872
Lansing lime	3024
Zone I	3050-55
Zone II	3110-12
Zone III	3122-34
Zone IV	3188-93
Aruckle Dolomite	3298