


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **EL DORADO REFINING COMPANY**
 Farm- **Boxberger No. 5**

SEC. **32 T. 13 R. 14W**
 NW SE SW

Total Depth. **3311'**
 Comm. **3-9-53** Comp. **3-22-53**
 Shot or Treated.
 Contractor. **Aylward Drlg. Co.**
 Issued. **5-16-53**

County **Russell**
KANSAS



CASING:

8 5/8" 320' cem w/175 sx.
 5 1/2" 3304' cem w/75 sx.

Elevation. 1860 DF

Production. **240 Bbls.**

Figures indicate Bottom of Formations.

surface clay	20
sand, shale	35
shale, shells	225
shale	315
hard sand, iron	340
white sand	380
part iron	435
shale, shells	760
shale, red bed	820
shale	880
sandy lime	934
red bed, shale	1225
red bed, salt	1325
shale, shells	1520
shale	1695
lime	1710
shale, shells	1830
lime w/shale	2250
shale	2275
shale, shells	2445
sandy shale	2530
shale, lime	2895
lime	2955
lime, shale	3085
lime	3140
lime, shale	3179
lime	3311

Total Depth

Tops DF	
Heebner	2974
Toronto	2992
Lansing	3028
Arbuckle	3299

DST 3299-3302, open 1 hr., weak blow 20 min., rec. 5' mud, BHP 0#.

DST 3300-3305, open 1 hr., rec. 7' mud BHP 800#.

DST 3300-3309, open 1/2 hr., strong blow rec. 560' oil & 10' HO&GCM BPH 1000 #/15 min.

D. P. & C. O. to RTD. 3309 DF est. 12 ROPH & 3% wtr. 1900' FTH/4 hrs.