

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - CITIES SERVICE OIL COMP NY  
Farm - Boxberger "A" No. 3

SEC. 32 T. 13 R. 14W  
SW NE NW  
990' S - 990' W of N $\frac{1}{4}$  corner

Total Depth. 3307'  
Comm. 10-19-47 Comp. 11-3-47  
Shot or Treated.  
Contractor. R. W. Rine Drilling Company  
Issued. 1-31-48

County. Russell

KANSAS



Elevation. 1872 Ind.

Production. Pumped 137 BO &  
3% wtr, 8 hours.

CASING:

8-5/8" 652' Cem. w/225 sx  
5-1/2" 3304' Cem. w/150 sx

Figures Indicate Bottom of Formations.

shale & shells	0-390
iron	420 ✓
sand & pyrite	565 ✓
shale & shells	652
shale, shells, sand & pyrite	920 ✓
anhydrite	950
shale, shells & sand	1135
shale & shells	1465
shale & lime	1850
lime	1910
shale & lime	2005
shale	2190
shale & lime	2325
shale & shells	2470
shale	2755
lime	2830
shale & lime	3175
lime	3309
3309 RTD= 3306' SLM	
lime	3307
Total Depth	

Tops:

Lansing corr.	3036
Arbuckle corr.	3304
Penetration	3

Fillup:

1400' oil in  $\frac{1}{2}$  hour..  
1830' oil in 1 hour..  
2400' oil in 3 hours..  
2630' oil in 6 hours..