

July, 1942

Harbour, # 1 Sutton Estate
(Samples, Cities Service, # 1 Sutton Estate)
SE/c. 7-13S-14W
Elev. 1648'

Rotary dry hole.

Pennsylvanian conglomerate

None. Cover is marine limestone, white,
mottled red, and with red shaly partings.

Arbuckle Top 3090'

Penetration 28'

Subsea -1442'

Cotter 3090'-3118' TD

3090-3107 Dolomite, white and light brown, medium
to coarse. Samples poor due to coring.
Scouts report core information as follows:

Cored 3092'-3102'

Rec. 8' hard dolomite with spotty saturation.
Rec. 2' oolitic dolomite with slight stain.

Cored 3102-3107'

Rec. 4½' dolomite, slight stain.

3107-3118 Dolomite, brown, white, rare red, coarse,
some medium. From 2 to 5 % bluish
transparent chert.

RFW & ML