

Empire, # 7 Ehrlich
NE SW SE, 28-13S-14W
Elev. 1863

Cable tool below 3278 equals
3279' corr.

Pennsylvanian Conglomerate

Basal foot or two of limestone is somewhat sandy

Arbuckle Top 3280' Penetration 26' Subsea -1417'

3280-3288 Friable coarse sand. Somewhat silicified at top. Boyce.

3288-3294 Dolomitic sand, medium, and sandy dolomite.

3294-3304 Dolomite, brown, fine to medium, very sandy. Sand grains are well sorted, fine to medium, faceted. Base Boyce 3304' or -1441'

3304-3306 Dolomite, brown, fine to medium. Pre Boyce.
