

**KANSAS DRILLERS LOG**

S. 36 T. 13 R. 15W <sup>E</sup>/<sub>W</sub>

Loc. SW SE NE

County RUSSELL

API No. 15 \_\_\_\_\_  
County \_\_\_\_\_ Number \_\_\_\_\_

Operator  
OIL INVESTMENTS, LTD.

Address  
316 Main Street, Russell, Kansas 67665


Well No. 1 Lease Name Boxburger

Footage Location  
feet from (N) (S) line \_\_\_\_\_ feet from (E) (W) line \_\_\_\_\_

Principal Contractor Revlin Drlg., Inc. Geologist Kenneth Vehige

Spud Date 1-6-80 Total Depth 3350' P.B.T.D. \_\_\_\_\_

Date Completed 1-13-80 Oil Purchaser \_\_\_\_\_



Elev.: Gr. \_\_\_\_\_  
DF \_\_\_\_\_ KB 1880'

**CASING RECORD**

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	242'	Quick-Set	140	
Production	7 7/8	5 1/2	15 1/2#	3349'	Common	100	5% Gilsonite 10% Salt 3/4 of 1% CFR2

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____ CFPB	
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator OIL INVESTMENTS, LTD		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Boxburger	Oil
S <u>36</u> T <u>13</u> R <u>15</u> W <sup>E</sup> / <sub>W</sub>		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay	0	40		
Shale - Shells	40	242		
Shells & Shale	242	315		
Shale	315	920		
Anhydrite	920	959		
Shale	959	1050		
Shale	1050	1610		
Shale	1610	1780		
Lime W/Shale	1780	2020		
Lime	2020	2210		
Lime & Shale	2210	2355		
Lime W/Shale	2355	2536		
Shale & Lime	2536	2609		
Lime W/Shale	2609	2730		
Lime	2730	2781		
Lime	2781	2865		
Lime	2865	3000		
Lime	3000	3076		
Lime	3076	3100		
Lime	3100	3105		
Lime	3105	3180		
Lime	3180	3280		
Lime & Arbuckle	3280	3350	R.T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Bookkeeper, Revlin Drlg., Inc. Title
	January 14, 1980 Date