

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG


State Geological Survey
 JUL 8 0 1980
 WICHITA BRANCH

S. 1 T. 13 R. 15 ^K _W

Loc. 50' W/SW NE NE

County Russell

640 Acres
N



Locate well correctly

Elev.: Gr. 1618'

DF _____ KB 1623'

API No. 15 — 167 — 21,419
County Number

Operator
Mai Operations

Address
Box 33 Russell, Kansas 67665

Well No. #5 Lease Name S & S Ranch "B"

Footage Location
990 feet from (N) SW line 990 feet from (E) SW line

Principal Contractor Emphasis Dlg. Geologist F. Whisler

Spud Date 3-13-80 Date Completed 3-22-80 Total Depth 3110' P.B.T.D. 3089'

Directional Deviation _____ Oil and/or Gas Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Csg.	12 1/4"	8 5/8"	28	690'	Quickset	600	Common
Oil String	7 7/8"	5 1/2"	14	3109'	Pozmix	125	LA-88, 2% Gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	J. Jets,	2800'-2982' L.K.C. 2800'-2982'

TUBING RECORD

Size 2" EU. Setting depth 3085' Packer set at none

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
<u>8500 Gal. plus 1200# Div. agent</u>	<u>2800' - 2982'</u>

INITIAL PRODUCTION

Date of first production <u>6-15-80</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil <u>3.5</u> bbls.	Gas _____ MCF	Water <u>100</u> bbls.	Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Mai Operations

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Oil Well

Well No.

5

Lease Name

S & S "B"

S 1 T 13 R 15^{NE} W

Russell, County

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
See Attached Drlrs. Log				
Geological Tops				
Anhy. 682' Topeka 2515' Heebner 2744' Toronto 2765' L.K.C. 2798' B.K.C. 3050' Marn. 3060' Arb. 3065' R.T.D. 3110'				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. E. Walz

Signature

Supt.

Title

6-27-80

Date

