


W. C. MCBRIDE, INC.
Gregg No. 1.

SEC. 24 T. 13 R. 15W
NEo SE
330' fr E & N Lines E $\frac{1}{2}$ SE $\frac{1}{4}$

Total Depth. 3227'
Comm. 2-12-40 Comp. 3-22-40
Shot or Treated.
Contractor.
Issued. 5-4-40 Cable O-3227

County. Russell



CASING:
15 $\frac{1}{2}$ " 300' 85/8" 2440'
13 3/8" 540' 7" 2954'
10 $\frac{3}{4}$ " 840' 5 1/2" 3216'

Elevation.

Production. Pot. 449 B.

Figures Indicate Bottom of Formations.

boulders	5	lime	1765	lime	2930
shale(10BW 100-45)	100	shale	1780	red rock	2935
shale sdy	145	lime	1850	shale	2948
red rock	165	shale	1860	lime	2950
shale	180	red rock	1870	2950=2954 SLM	
red rock	205	lime	1890	lime	2968
sand HFW	210	shale	1895	shale	2975
shale	270	lime	1920	lime	2980
sand	295	lime brkn	1950	small sh oil & wtr	
iron	300	lime	1970	lime	3000
sd iron	315	lime brkn	1985	sm sh gas&oil-1BW 2995-3000	
iron	345	shale blue	1995	lime	3028
gravel	355	lime	2010	shale	3033
sand	360	lime brkn	2025	small sh oil	
iron	365	lime	2050	lime	3038
shale	405	lime brkn	2075	HFW	
sand	425	lime	2100	lime	3050
shale	445	shale	2105	lime	3093
sand	470	lime	2130	shale	3095
shale	485	lime brkn	2140	lime	3146
shale red	515	lime	2165	shale	3150
sand	530	red rock	2175	lime	3158
shale red	533	lime	2195	shale	3161
sand	538	shale	2195	lime brkn	3170
shale red	540	lime	2205	lime	3188
shale(1BW 625-35)	545	shale	2210	shale	3192
shale red	635	shale & shells	2230	lime	3203
shale red sdy	650	shale	2325	shale	3208
shale red(more wtr660)	660	lime	2345	lime	3211
shale red sdy	735	shale	2352	shale(SLM 3218=3217)	3218
more wtr@700 7BWP	815	red rock	2360	lime (sm sh oil 3223)	3227
shale red	835	shale	2365	Increase in oil 3226-27	
anhydrite	840	shale blue	2385	Total Depth,	
lime	845	lime	2418		
anhydrite	870	lime brkn	2420		
lime	875	shale	2435	Top K.C. lime 2954 SLM	
red rock	995	lime	2472	Arbuokle 3216-27	
shale	1060	shale	2478		
red rock	1115	shale	2490	Oil stain 2954-61	
shale	1190	lime	2505	sm sh oil & wtr 2975-80	
lime	1200	shale & shells	2535	sm sh gas & oil & 1BW 2995-	
shale	1205	shale	2565	3000	
lime	1210	lime	2570	sm sh oil 3028-33	
shale	1250	shale	2615	HFW 3033-38	
salt	1470	lime	2620	Pay 3226-27	
shale & shells	1510	shale & shells	2630		
shale	1520	shale	2635	1800' OIH in 10 hrs	
lime	1530	lime	2660		
shale	1535	shale	2675	3-24-40 300 Gals.	
lime	1550	lime(sm sh oil 2720)	2695	3-25-40 400 Gals.	
shale	1555	shale & lime	2720		
lime	1565	lime brkn	2730		
shale	1570	lime	2755		
lime	1595	shale	2760		
red rock	1600	lime	2800		
lime	1625	shale & lime	2825		
shale & shells	1635	lime	2845		
lime	1645	lime brkn	2850		
shale	1670	lime	2890		
lime	1715	shale	2900		
red rock	1725	lime	2905		
		shale & shells	2920		