

✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **BARTON BROS. OIL PRODUCERS**
Farm- Atherton No. 2

SEC. 25 T. 13 R. 15W
SW SW SE

Total Depth. 3310'
Comm. 12-22-61 Comp. 1-1-62
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 7-6-63

County Russell

KANSAS



Elevation. 1889' RB

Production. 25 BOPD

CASING:

8 5/8" 929' cem w/450 sx.
5 1/2" 3305' cem w/175 sx.

Figures Indicate Bottom of Formations.

shale & shells	410
iron pyrite & sand	465
shale & shells	500
redbed & shale	914
Anhydrite	1420
shale & shells	1670
lime & shale	2855
lime	3310RTD
Total Depth	

TOPS:	
Topeka	2765
Heebner	2990
Toronto	3008
Lansing	3042
Arbuckle	3308

DST #1 3045-60' Tool op 1 hr. w/weak blow for 4 min. Rec. 10' mud. All pressures 0#.

DST #2 3052-92' Tool op 1 hr. w/weak blow thruout. Rec. 520' gas, 120' 0 & GCM.