

92-13-15W
SM

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

Plotted Texas CO.


BRIDGEPORT MACHINE CO.
J. E. Baxter No. 16.

SEC. 32 T. 13 R. 15W
SEC SE

JUN 16 1934

County, Russell.

Total Depth. 3115.
Comm. 12-20-33 Comp. 3-14-34.
Shot or Treated.
Contractor.
Issued. 6-16-34
CASING.



15 1/2" 425' 8 1/2" 2820'
12 1/2" 640' 6 1/2" 3049'
10" 937' 53/16" 68' liner.

Elevation.

Production. Potential.
224 bbls per day.

Figures Indicate Bottom of Formations.

cellar	10	sdylime white H.	2015	slight sh oil 3049 1/2
sand yellow	15	shale blue soft	2035	Top Oswald lime 3049
shale dark	195	lime grey hard	2050	lime med 3051 1/2
sand white	225	shale grey soft	2060	show oil nowater.
shale blue	240	lime white hard	2080	lime hard 3066
shale pink	252	shale red soft	2105	broken lime & shale 3071
sand white	275	slate grey soft	2120	shale blue 3074
shale pink	285	lime white hard	2135	Reduced hole 3074
sand white	380	slate grey soft	2145	lime hard 3076
shale light	390	shale red soft	2162	lime soft 3083
shale blue	465	lime grey hard	2215	Pay hole filled up 800'
sdylime grey	480	shale red soft	2230	with oil.
shale blue	496	lime grey hard	2255	lime hard 3092
iron dark hard	500	shale blue soft	2265	lime soft 3098
sand red	565	lime white hard	2325	lime hard 3115
shale red soft	613	shale blue soft	2331	T.D.
sand red soft	635	lime white hard	2342	
shale red rock	725	shale blue soft	2380	Slight increase of gas.
sand red soft	735	lime white hard	2415	
4 BWPHR		shale brown soft	2425	
shale red rock	880	lime shell grey Hd.	2430	Lead Plug driven filling
sand red soft	885	shale blue soft	2440	hole back up to 3111' BH
shale red soft	927	sdylime wh S. wtr	2450	Well acidized - produced
shale and chalk	934	shale dark soft	2497	13 bbls per hr 1st 24Hr
anhydrite of lime H.	971	lime grey hard	2505	after head was pumped
shale red soft	1133	shale blue soft	2555	off. Was pumped 5 days
shale blue soft	1160	lime shell grey Hd.	2558	at reduced speed then a
shale brown soft	1240	shale blue soft	2565	7 day potential test
shale blue soft	1265	lime grey hard	2582	made which averaged 224
slate grey soft	1315	shale blue soft	2590	bbls per day.
lime shell grey hard	1320	lime grey hard	2600	
salt soft	1555	shale blue soft	2620	
shale blue soft	1582	lime grey hard	2635	
lime grey hard	1598	shale blue soft	2650	
slate grey med	1602	lime shell wh hard	2652	
lime grey hard	1611	shale blue soft	2710	
lime and shale med	1620	lime grey hard	2735	
lime white hard	1630	slate grey med	2750	
shale grey soft	1640	lime white hard	2795	
lime white hard	1655	show of oil 2750-2755.		
shale grey soft	1665	hole corrected from		
lime white hard	1695	2760 to 2790		
shale red soft	1710	shale grey med	2800	
lime wh hard	1740	lime white hard	2900	
shale blue soft	1745	lime grey med	2920	
shale red soft	1755	lime white soft	2930	
shale blue soft	1775	1 BWPHR		
lime grey hard	1810	lime white hard	3005	
shale red soft	1840	shale blue soft	3013	
lime white hard	1994	lime white hard	3031	
shale blue soft	2000	shale red soft	3040	