

32. 13. 15W


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - ANDERSON PRICHARD OIL CORP.
Farm - Memis No. 1

SEC. 32 T. 13 R. 15W
NW NE NW

Total Depth. 3348
Comm. 12-30-49 Comp. 1-18-50
Shot or Treated.
Contractor. Lindas Oil, Inc.
Issued. 3-25-50

County. Russell
KANSAS



Elevation. 1910 (m)
1913 R.B. (check)

Production. Pot. 79 bbls oil
and 39 water

CASING:

8 5/8" 352'
5 1/2" 3335'

Figures Indicate Bottom of Formations.

post rock	25
sand	40
shale blue	265
sand	295
shale blue	352
shale	440
sand	560
shale, sand, iron	690 ✓
sand, iron	715 ✓
red bed	957
anhydrite lime	990
shale, shells	1275
salt	1430
salt, shale	1495
shale, shells	1635
lime, shale	1650
lime brkn	1735
lime	1840
lime brkn	1940
lime	2175
lime, shale	2415
shale, lime shells	2470
lime, shale	2640
shale, shells	2725
shale, lime	2810
lime	3280
lime brkn	3325
lime, shale RTD	3335
lime	3348
Total depth	

Tops:
Topeka 2802
Heebner 3025
Lansing 3070
Gorham sand 3332