

Location *W* NW/4 SW/4

Sec. 33 T. 13 R. 15W.


Casing Record

20" 10" Farm- J. A. Mermis No. 1 County Russell
 15 1/2" 8 1/2" Company- Stearns-Streeter Co.
 12 1/2" 65/8" Contr.-
 12 1/2" 53/16" Comm.- 11/12/27. Comp.- 1/29/28.

FEB 13 1928

Total Depth 3317'.

Correspondence Regarding This Well Should Be Referred to



Elevation 1847

Initial Production 50
bbls. per hr.

Figures Indicate Bottom of Formations.
Date Issued. 2/11/28.

Formation	Depth	Formation	Depth	Formation	Depth
soil	10	slate grey	2150	Show of Oil at 3091'	
shale	25	lime white	2180	lime	3093
sand	30	red rock sft	2195	shale	3097
shale	270	lime hrd	2245	lime	3140
red rock	299	slate grey	2265	Good show of oil at 3139'	
shale blue	325	lime grey	2275	water sand	3143
sand	405	Caving some		2 B" 3140-3143'	
shale	465	shale blue	2295	lime	3183
slate blue	475	lime grey	2345	slate blue	3187
sand	495	slate blue	2360	lime white very hrd	3210
slate blue	520	lime shells	2370	brkn lime	3227
sand grey	535	slate grey	2380	red shale	3231
slate brown	580	lime	2390	lime brkn	3241
sand grey	585	slate blue	2423	lime	3248
red rock	625	lime	2431	shale blue	3262
Set 15 1/2" at 605'		caving badly at 2431'		lime	3265
UR from 441' to 605'		slate grey	2475	Hole caving	
sand HFV 625'	645	slate pink	2485	lime shells &	
red rock	946	lime sandy	2495	slate	3287
chalk	958	slate blue	2507	lime	3297
Top of lime		slate grey	2525	SLM correction	3312
Set 12 1/2" at 954'		Fighting cave		Hole caving	
lime	997	Bailing water		Straight reamed from	
red rock	1140	slate blue	2535	3091 to 3312'	
slate grey	1200	lime	2543	Set 5 3/16" at 3312'	
red rock	1295	slate blue	2560	lime shell	3314
slate grey	1325	Caving badly at 2550'		Pay sand	3317
shelly lime &		brkn lime	2580	Total Depth SLM	3317&
grey slate	1355	slate grey	2727		
salt	1580	lime hrd	2741		
slate blue	1590	lime brkn	2750		
Set 10" at 1590'		slate grey	2760		
lime	1593	lime	2772		
slate drk	1599	lime white	2782		
lime grey	1607	slate grey	2787		
slate grey	1620	lime	2806		
lime grey	1660	slate grey	2816		
lime	1724	Showing of oil 2845'			
shale brown	1740	lime	3022		
lime grey	1775	1 1/2 B" at 2985'			
slate grey	1790	shale	3026		
lime white	1820	lime Dodge	3030		
shale brown	1853	shale	3034		
lime white	1940	SLM correction Dodge			
slate grey	1945	lime	3032		
lime hrd	1980	lime	3047		
red rock	1985	shale brown	3062		
lime	2015	SLM Top of Oswald	3063 1/2'		
slate grey	2023	lime Oswald	3070		
lime	2045	shale	3073		
shale	2050	lime sft	3088		
brkn lime	2065	6 B" 3076 to 3088'			
lime hrd	2100	lime hrd	3091		
brkn lime	2110	Set 6 5/8" at 3090'			
lime brown	2135	UR showing water at 3091'			