

33. 13. 15W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG WICHITA, KANSAS. **Plotted Texas CO.**

Location **NE SW SW .** DRILLED WITH STANDARD TOOLS Sec. 33 T. 13 R. 15W.

Casing Record
 10" 940 Farm- Mernis (Gorham Field) No. 11 County- Russell.
 20" 8 1/2" 2623 Company- Keys Petroleum Co.
 15 3/8" 405 65/8" 3044 Contr.- Keys.
 12 3/8" 575 53/16" Comm.- 9/18/30 Comp.- 11/9/30.
 Total Depth 3115' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to

DEC 15 1930



Figures Indicate Bottom of Formations.
 Date Isued. 12/13/1930'.

Elevation
 Initial Production
 120 bbls per day.

Formation	Depth	Formation	Depth	Formation	Depth
surface	15	lime	1840	lime	2710
sand yellow	30	shale	1850	8" csg. at 2714'	
shale blue	60	lime	1870	shale blue	2720
shale brown	125	4 BW at 1860'		lime	2725
shale blue	215	shale gray	1890	shale blue	2730
sand HFW	230	shale white	1915	lime	2750
shale white	240	lime	1940	Show oil at 2776'	
shale brown	260	shale	1945	shale blue	2780
sand water	280	lime	1965	lime	2945
red rock	320	shale	1980	shale blue	2950
sand	340	lime brkn	2030	lime	3005
red rock	350	shale	2060	1 1/2" BW at 2990'	
sand	360	lime	2085	shale	3010
red rock	365	shale	2095	shale blue	3012
shale blue	390	lime	2105	lime	3032
sand	395	red rock	2115	shale brown	3039
shale blue	460	lime	2130	Ran 6" csg. 3044'	
sand	465	shale	2140	shale brown	3044
shale blue	505	lime	2160	lime	3065
sand	520	red rock	2185	shale blue	3072
shale red	560	lime	2240	lime	3115
red rock	575	red rock	2245	Oil at 3072-80'	
shale red	600	lime	2270		
sand HFW	625	shale gray	2275	Total Depth	3115'
red rock	685	lime	2300		
shale red	900	shale	2310	Complete 5 bbls per hr.	
red rock	940	lime	2330		
lime	995	shale	2345		
red rock	1140	lime	2380		
shale blue	1170	shale	2415		
red rock	1230	lime	2425		
shale blue	1250	shale	2440		
red rock	1265	8" at 2430'			
shale	1315	lime	2445		
salt	1570	shale	2460		
shale	1575	lime	2470		
lime	1590	shale	2490		
shale	1600	lime	2500		
lime	1625	shale black	2525		
shale	1630	lime	2537		
lime	1650	shale black	2565		
shale gray	1660	shale black	2568		
lime	1670	lime	2605		
shale	1695	shale	2615		
lime	1705	lime	2635		
red rock	1720	8" at 2623'			
lime	1755	shale blue	2640		
shale	1740	lime	2665		
lime	1815	shale gray	2690		
red rock	1825	shale black	2705		