

34. 13. 15W

A.H.WITT
Baier No. 1.SEC 34 T. 13 R. 15W.
SE SW SE


Plotted Texas CO.

County Russell

Total Depth. 3350
Comm. 9-22-37 Comp. 11-4-37
Shot or Treated.
Contractor.
Issued. 2-5-38

CASING.

FEB 5 1938



15 1/2"	349' 4"
12 3/4"	647'
10"	950'
8 1/4"	2550'
6 5/8"	3306'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

cellar	10	red rock soft	1730	shale blue soft	2533
clay yellow	50	lime white hard	1760	lime white hard	2540
shale grey	115	shale blue soft	1775	shale dark soft	2545
shale dark	190	shale grey	1790	lime white hard	2555
shale blue	200	lime grey med	1820	shale light sft	2590
shale grey	218	shale brown	1830	lime white hard	2605
sand white	230	lime med	1840	shale light	2615
shale grey	240	red rock soft	1846	lime light	2630
sand grey	255	lime grey hard	1855	shale	2640
shale dark soft	265	sdylime brown med	1865	lime white hard	2675
sand	315	lime white hard	1890	lime white mod	2685
shale yellow	330	shale blue soft	1895	shale light soft	2730
sand	340	lime	1970	lime white hard	2745
shale blue tough	385	red rock	1980	shale blue hard	2755
shale light soft	395	lime wh hard	2014	lime white hard	2780
shale dark soft	415	shale soft	2018	shale blue soft	2793
sand grey	440	lime white hard	2045	lime white hard	2935
shale blue soft	510	shale light soft	2060	shale blue soft	2940
sand grey soft	530	lime white hard	2110	lime white hard	2990
sand yellow hard	550	red rock	2115	lime grey hard	3017
sand white soft	565	lime white	2145	shale blue	3020
shale blue soft	580	shale blue soft	2148	lime grey hard	3025
red rock soft	605	lime white hard	2165	shale blue	3033
shale red soft	615	shale light soft	2185	1/2 B.W. 3033-43	
sand red med	642	red rock soft	2195	Dodge lime wh hard	3051
shale red	647	lime white hard	2225	red rock soft	3055
red rock soft	685	shale blue	2230	shale	3070
shale red soft	770	lime	2245	lime grey mod	3090
red rock soft	942	red rock	2255	Oswald lime	3100
anhydrite lime wh hd	985	lime light hard	2280	lime grey hard	3245
red rock dark	1130	shale shells blue sft	2295	1/2 B.W. 3180-85	
shale blue soft	1165	lime white hard	2325	shale red soft	3249
red rock soft	1215	shale light soft	2335	showing oil 3190-95	
shale blue soft	1310	lime white hard	2345	lime grey hard	3275
salt white med	1340	shale	2350	shale soft	3285
salt light med	1400	lime	2355	lime white hard	3300
salt grey med	1545	shale	2360	shale blue soft	3303
salt white med	1595	lime white hard	2370	lime grey hard	3319
shale blue soft	1600	shale blue soft	2380	shale	3323
salt grey hard	1615	lime white hard	2420	showing oil 3328	
shale blue soft	1625	shale blue soft	2425	lime grey hard	3350
lime grey hard	1635	lime white hard	2450	showing oil 3332-34	
shale light soft	1640	red rock	2455	Total Depth.	
shale blue	1650	shale	2460	Well plugged.	
lime white hard	1655	lime	2475		
shale blue	1660	shale red	2485		
lime white hard	1705	shale blue soft	2492		
shale blue soft	1712	lime white hard	2495		
lime white hard	1718	sdylime blue sft	2520		