

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

34.13.15
g. e. f.

CENTRAL PETROLEUM CO.
Mills No. 1.


SEC. 34 T. 13 R. 15W.
SW₂ SW
330' B 330' E. Fr. SW₂ SW₂

Total Depth. 3319
Comm. 12-14-38 Comp. 1-15-39
Shot or Treated.
Contractor. Harry Gore.
Issued. 2-25-39

County Russell.

CASING.

15 1/8"	380'
12 1/2"	625'
10"	935'
8 1/4"	2775'
6 5/8"	3085'
5 3/16"	3316'



Elevation.

Production. Pot. 363 B.

Figures Indicate Bottom of Formations.

cellar	8	limo	2165	limo	3290
shaly shale	20	red rock	2175	shale blue	3298
shale blue	200	limo	2230	limo	3302
shale grey	215	red rock	2240	shale	3316
shale sdy	235	limo	2250	limo (oil pay)	3319
slate	245	shale and shells	2395	Total Depth.	
shale yellow	260	limo	2412		
shale white	275	slate blue	2470	limo (Oil pay)	3316-3319
sand water	290	limo	2475		
red rock	305	shale sdy	2490	5 BW 220	
slate blue	390	shale and shells	2510	HFW 280-90	
shale grey	410	limo	2520	HFW 455-470	
shale blue	455	shale blue	2565	4 BW 725	
sand water	470	limo	2582	9 BW 790-810	
iron	475	shale blue	2590	1/4 BW 1330	
sand shale	500	limo	2620	Little water	2130-45
sand water	555	shale blue	2640	1 BW 2485	
red rock	790	limo	2650	1/2 BW 2960-65	
sand water	810	shale blue	2665		
red rock	925	limo	2675	Anhydrite	925-965
lime Anhydrite	965	shale blue	2713	Oswald Top	3061
red rock	1105	limo	2725	Gorham sand	3316-3319
shale blue	1140	shale blue	2730		
red rock	1265	limo	2745	hole filled	2700' with oil
salt	1585	shale blue	2750	after standing	24 hours
shale blue	1600	limo	2753	after drilling in.	
slate and shells	1665	shale	2772		
lime	1680	limo	2860		
shale blue	1685	shale blue	2865		
lime	1705	limo	2897		
red rock	1725	shale blue	2903		
lime	1755	limo	3000		
shale	1780	shale blue	3010		
lime	1820	lime (Dodgo)	3025		
red rock	1840	shale	3028		
lime broken	1915	shale red	3032		
shale blue	1920	shale blue	3061		
lime	1930	lime Oswald	3078		
shale blue	1935	shale	3085		
lime	1960	limo	3195		
red rock	1970	shale blue	3200		
lime	1985	limo	3235		
shale blue	2015	various shale	3245		
limo	2025	limo	3260		
shale blue	2040	shale	3265		
lime	2080	shale and shells	3275		
shale blue	2085	limo	3280		
red rock	2095	shale blue	3285		