

35. 13. 15W

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY FRED J. HAYNES

SEC. 35 T. 13 R. 15W

FARM Dillner

NO. 1

LOC. SW NE NE

TOTAL DEPTH 3312

COUNTY Russell


COMM. 11-12-50

COMP. 12-29-50

SHOT OR TREATED

CONTRACTOR

ISSUED 2-3-51



1881 gnd.

ELEVATION

PRODUCTION 60 BOPD

CASING

15" 395'
12" 580'
10" 930'
8" 2560'
7" 3065'
5" 3255'

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar, post rock 20
shale 225
sand 240
shale 280
sand 290
shale 455
shale, iron 555
red rock 930
anhydrite 967
red rock 1160
shale 1310
salt 1540
shale, shells 2772
Topeka 2995
shale, shells 3018
Dodge 3032
red rock 3035
shale blue 3052
K. C. 3295
shale 3299
lime 3301
shale 3306
lime 3312
Total Depth

Tops:

Anhydrite 967
Tarkio 2463
Topeka 2772
Heebner 3000
Dodge 3018
Kansas City 3052
Arbuckle 3306 ?

Water:

HFW 225
1/2 BW 2955
HFW 3135

Oil & Gas:

gas 2463
SO 2955
SO and water 3075
SO 3115
SO 3215
SO 3265
Good SO 3310