

36-13-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ICER ADDIS
Farm- Boxberger No. 1

SEC. 36 T. 13 R. 15
SW NW SE

Total Depth. 3360'
Comm. 9-7-60 Comp. 9-18-60
Shot or Treated.
Contractor. Triangle Drlg.
Issued. 2-25-61

County Russell
KANSAS



CASING:
8 5/8" 909' cem w/410 sx.
5 1/2" 3317' cem w/100 sx.

Elevation. 1872' KB

Production. SWDW

Figures Indicate Bottom of Formations.

clay & post rock	90
shale & clay	180
shale & sand	205
shale	295
shale & sand	535
red bed	903
Anhydrite	941
shale & shells	1570
limestone & shale	1925
limestone	2020
limestone	2754
limestone	3016
shale	3032
limestone	3295
sand	3304
dolomite	3360 RTD
Total Depth	

TOPS:

Anhydrite (driller's)	903
Heebner	2982
Toronto	3002
Lansing	3032
Gorham Sand	3295
Arbuckle	3304