

15-167-21047

State Geological Survey  
WICHITA BRANCH  
KANSAS DRILLERS LOG

API No. 15 — 167 — 21,047  
County Number

S. 36 T. 13 R. 15 <sup>R</sup>/<sub>W</sub>  
Loc. N2 S2 SE  
County Russell

Operator  
Allen Drilling Company

Address  
P. O. Box 1389 Great Bend, Kansas 67530


Well No. #2 Lease Name Boxberger

Footage Location  
500 feet from (N) (S) line 600 feet from (E) (W) line

Principal Contractor Allen Drilling Company Geologist Kenneth Vehige

Spud Date 4-12-77 Total Depth 3308' P.B.T.D.

Date Completed 5-3-77 Oil Purchaser



Elev.: Gr. 1871  
DF 1873 KB 1876

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	28#	906'	60/40 Pozmix common	200	2% gel 2% cc.
	7 7/8"	5 1/2"	14#	3307'	25 sx 50/50 Pozmix 800 gal. Latex	200	2% gel 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jet 15/32	3074-76
			4	Jet 15/32	3033-34

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 15% Reg. Acid	3074-76
500 gal. 15% Reg. Acid	3033-34

INITIAL PRODUCTION

Date of first production Dry Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

Lease Name

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ E \_\_\_\_\_ W \_\_\_\_\_

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>0- 903' Sand and Shale            903- 940' Anhydrite            940-1115' Red Bed            1115-1745' Shale            1745-2753' Shale and Lime            2753-2905' Lime            2905-2978' Limestone, cream light gray            2978-2998' Shale            2998-3280' Lime            3280-3303' Sand, lear quartz            3303-3308' Dolomite            3308' RTD</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Earl Allen*  
Signature

President

Title

April 19, 1977

Date