

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


36-13-15W

Company- ICER ADDIS, M. HILL ET AL
Farm- Boxberger "A" No. 1

SEC. 36 T. 13 R. 15W
SW NW SE

Total Depth. 3327'
Comm. 7-29-53 Comp. 9-16-53
Shot or Treated.
Contractor. Shields & E. Spudder
Issued. 2-23-57

County Russell
KANSAS



CASING:
12 1/2" 446' 5 1/2" 3312' w/75 sx cem.
10" 906'
8 1/4" 2475'
7" 3074'

Elevation. 1873'

Production. 25 BOPD

Figures indicate Bottom of Formations.

cellar	8	slate	1990	lime	2997
yellow sandy		lime	2025	Heebner shale	3000
clay	20	slate	2033	lime	3003
slate	178	lime	2075	slate	3013
sand	205	redrock	2080	Dodge lime	3031
slate	225	lime	2155	redrock	3035
sand HFW	245	redrock cave	2168	slate	3044
slate	250	lime	2195	lime, Lansing	
Redrock	257	slate	2200	& Kansas City	3085
slate	270	lime	2227	slate	3086
sand	283	slate	2234	lime	3114
redrock	293	lime	2255	slate	3115
slate	305	slate	2265	lime, show of	
redrock	315	lime, broken	2275	oil & gas	3177
slate	340	lime	2295	slate	3180
sand	350	slate	2300	lime, show of	
sand	370	lime	2310	oil & gas	3235
slate	432	slate	2315	slate	3268
sand & Iron	440	lime, broken	2345	lime	3308
slate	465	slate	2350	slate, cave	3312
sand HFW	478	lime, broken	2363	lime	3319
slate	515	lime	2372	oil Pay, Quartz	
sand	530	slate	2395	Sand	3327
slate	536	lime	2405	Total Depth	
Redrock	904	slate	2420		
Anhydrite lime	947	redrock	2431	TOPS	
Red rock	1105	lime broken	2440	Tarkio	2475
slate	1145	lime	2455	Topeka	2770
red rock	1200	sandy shale	2469	Heebner	2997
slate	1210	lime	2471	Toronto	3013
Red rock	1220	sandy shale	2480	Lansing/Kansas	
salt	1565	Trakio Sand		City	3044
slate	1570	show of oil	2492	Gorham Sand	3319
lime	1575	lime, sandy	2495		
slate	1589	slate cave	3515		
lime	1600	lime	2527		
slate & shells	1623	shale & shells	2535		
lime	1640	slate	2568		
slate	1650	lime	2583		
lime	1665	slate	2585		
slate	1673	lime	2595		
lime	1692	slate	2600		
brown slate	1705	lime	2695		
lime	1740	slate	2614		
slate	1750	lime	2625		
red rock	1760	slate	2635		
lime	1798	lime	2640		
slate	1803	slate & shells	2670		
red rock	1830	slate	2709		
lime	1868	lime	2725		
slate	1872	shale & shells	2745		
lime	1945	slate	2750		
slate	1950	lime	2758		
lime	1955	slate	2770		
redrock	1962	lime, Topeka	2785		
lime	1985	slate	2790		
		lime	2854		
		slate	2863		