

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


36-13-15W

SKELLY OIL CO.
F.L.Dillner No. 1.

SEC.36 T.13 R. 15 W
CE $\frac{1}{2}$ NW SW
660'f NL 990'f WL N $\frac{1}{2}$ SW $\frac{1}{2}$

Total Depth. 3308'
Comm. 8-22-42 Comp. 9-15-42
Shot or Treated.
Contractor. Claude Wentworth Drlg.Co.
Issued. 12-19-42 Rotary O-3306
Cable 3306-08

County. Russell



CASING:
10 $\frac{3}{4}$ " 308' Cam.
6" 3304 $\frac{1}{2}$ ' Cam.

Elevation.

Production. Pot.66 B.Min.

Figures Indicate Bottom of Formations.

surface soil, shale, shells	314	lime brown sdy &
red bed & shale	565	dolomitic, fair porosity
shale & shells	862	& saturation, 125' fluid
shale & red bed	920	in hole in 1 hr, showing
anhydrite	955	of sulphur wtr, 225' in
shale & red bed	1250	2 hrs, 400' in 5 hrs,
sdv shale	1551	1000 in 12 hrs, no inc.
shale	1565	in wtr - 1700' in 20
lime	1645	hrs showing 5% wtr 3308
lime & sand	1728	Total Depth.
shale	1762	
sand & shale	1792	
shale & lime	1878	Tops:
sand & shale	1922	Lansing lime 3053
shale	1925	Arbuckle lime 3304
sand & shale	1945	
lime & shale	1957	2946-56 med.oil sat.
lime	2030	3069-76 sli.por. & sat.
shale	2035	3091-94 sli.por. & stained
lime & sand	2043	3111-20 sli.por. & stained
lime & shale	2085	3198-3209 lgt sat.
lime	2145	3304-08 pay formation
shale	2186	
lime	2285	POB 16 hrs, 116 BO, 8 BW
sand & lime	2331	POB 3 hrs 22 BO, 1 BW to
shale	2555	estb. Min.Pot. 66 B.
lime	2603	
lime & shale	2705	
lime shells	2726	
lime & shale	2748	
shale	2764	
lime	2938	
shale & lime	3018	
brown porous oolitic &		
cryst.lime, med oil sat, 2946-56		
lime	3105	
med.hd oolitic lime 3069-76		
slight porosity & sat.		
med sft oolitic lime 3091-94		
slight porosity & sat.		
limo brkn	3114	
lime	3124	
slight porosity & sat. 3111-20		
lime cherty	3126	
shale & brkn lime	3132	
lime cherty	3155	
lime	3198	
lime sft, lgt saturation	3209	
lime	3214	
lime & shale	3227	
lime	3240	
lime brkn	3250	
lime	3304	
dolomite brown sdy &		
dense gy, finely cryst.		
dolomite, slight porosity		
& sat.	3306	
Drld cement plug, sh oil on		
CO to btm - Tested 2BOPH		