


BRIDGEPORT MACHINE CO.
Mills No. 4-B.

Plotted Texas Co.
SEC. 33 T. 13 R. 15W
NW SW SE

Total Depth. 3302'
Comm. 3-20-39 Comp. 5-9-39
Shot or Treated.
Contractor. Bridgeport Machine Co.
Issued. 6-10-39

County. Russell



CASING:
15 1/2" 309'
12 3/8" 630'
10 " 973'
8 1/4" 2570'
7 " 3044'
53/16" 3294'

Elevation. 1886

Production. Pot. 535 B.

Figures Indicate Bottom of Formations.

cellar	10	lime	2145
shale	45	red rock	2160
shale blue	90	lime	2220
clay blue	175	red rock	2270
shale grey	190	shale blue	2275
shale sdy	210	lime	2295
shale grey	240	shale	2300
shale white HFW	265	lime	2310
shale sdy	280	shale	2315
red rock	305	lime	2327
clay blue	320	shale	2335
shale blue	455	lime	2340
lime	460	shale	2390
shale blue	485	lime	2420
shale grey	510	shale	2430
red rock	535	lime	2435
sand wtr	540	shale	2500
red rock	605	lime	2510
sand	620	shale	2573
shale blue	627	lime	2600
red rock	780	shale	2610
sand red LBW 685	800	lime	2655
red rock 6BW 730	926	shale	2660
anhydrite	970	lime	2665
red rock	1120	shale	2695
shale	1160	lime	2750
red rock	1200	shale	2760
shale blue	1220	lime	2993
red rock	1230	small sh oil	2765
shale blue	1250	shale	3000
lime shells & shale	1275	lime	3005
shale	1280	shale	3010
salt	1570	lime Dodge	3022
shale blue	1575	red rock	3027
lime	1610	shale	3040
shale	1615	lime K.C.	3058
lime	1635	shale	3061
shale	1645	lime	3107
lime	1685	shale lgt	3110
red rock	1690	lime	3127
lime	1695	shale	3130
red rock	1705	lime	3170
lime	1745	shale	3180
shale blue	1755	lime	3195
lime	1800	lime	3203
shale	1805	shale	3206
lime brkn	1820	lime	3240
lime	1860	shale	3250
shale blue	1870	lime	3273
lime	1955	shale	3278
red rock	1959	lime	3287
lime	2020	shale	3290
shale blue	2035	lime	3295
lime	2055	granite	3302
shale	2060	Total Depth.	
lime	2095		
shale	2100	Oil 3295-3300	