

35.13.15W

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SHIELDS OIL PROD., INC.

SEC. 35 T. 13 R. 15W

FARM Johnson

NO. 1

LOC. SW NE SW

TOTAL DEPTH 3328'

COUNTY Russell


COMM. 8-29-65

COMP. 9-16-65

SHOT OR TREATED

CONTRACTOR Shields Oil

ISSUED 11-25-67



CASING

20	10	
15	8 5/8	254' w/165 sx cem.
12	6	
13	5 1/2	3326' w/100 sx cem.

ELEVATION 1898' KB

PRODUCTION DRY (ARB)

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil	40
shale, sand	102
shale, sand, shells	475
sand, shells, red rock	941
Anhydrite	980
shale, shells	1570
shale, lime	2010
lime	2050
lime, shale	2715
lime	3230
lime, chert	3328
Total Depth	

TOPS: SCOUT	SAMPLE
Anhydrite	941
Grand Haven	2464
Dry Shale	2470
Dover Lansing shale	2493
Lansing Shale	2497
Toronto Lansing shale	2537
Will shale	2554
Elmont	2586
Topeka	2789
Heebner	3014
Toronto	3035
Lansing	3071
Arbuckle	3324

DST No. 1 - 2495-2515, Rec.  
500' wtr & few oil specks.

DST N. 2 - 2790-2800', Rec. 10'  
oil specks.

DST No. 3 - 3318-28, Rec. 100'  
gas, 195' gassy oil, 15 wtr.