


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - RAPID DRILLING CO.
Farm - Foster No. 1

SEC. 7 T. 13 R. 15W
NE SW NE

Total Depth. 3342
Comm. 9-22-48 Comp. 10-20-48
Shot or Treated.
Contractor. Rapid Drilling Co.
Issued. 5-6-50

County. Russell
KANSAS



Elevation. 1886 *ft*

Production. dry

CASING:

8 5/8" 196' cem w/90 sx.
5 1/2" 3320' cem.

Figures Indicate Bottom of Formations.

surface soil, clay	35
shale, shells	140
sand, shells	165
shale	196
shale, shells	310
sand, shells	400
shale, sand, pyrite of iron	590 ✓
redbed, shells	640
sand	655
redbed	747
redbed, shale	956
anhydrite	995
redbed, shale	1150
shale, shells	1355
salt, shale	1530
shale	1570
shale, anhyd. strks	1585
shale	1625
anhyd.	1650
shale, lime	1760
lime	1855
lime, shale	1860
shale gummy	1880
shale, strks lime	2040
shale gummy	2075
lime	2085
shale, lime	2295
lime brkn, shale	2370
lime, shale	2480
shale sdy	2535
lime, shale	2855
lime	2970
shale, lime	3055
lime RTD	3329
lime	3342
Total depth	

Tops:

Anhydrite	954 DF
Kansas City	3047 "
Arbuckle	3320 "