

81
md

CONTRACTOR'S WELL LOG

21

OPERATOR: Petro-Pak Corporation
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: JACOB #1
LOCATION: C W/2 E/2 NE, Section 14-13S-15W
Russell County, Kansas
SPUD DATE: 6/04/81
COMPLETION DATE: 6/12/81

0	1385	Sand & Shale
1385	3048	Shale
3048	3286	Lime & Shale
3286	3286	Rotary Total Depth

Spud hole at 6:30 p.m., 6/04/81. Drilled 22' of a 12 $\frac{1}{4}$ " hole. Ran 5 jts. of 8 5/8" - 20# casing, Set @ 219.41', cemented with 170 sx. of common 3% Ca. Cl., 2% Gel. Cement did circulate. Plug was down at 12:30 a.m., 6/05/81.

T. . @ 3286'. Ran 77 jts. of 4 $\frac{1}{2}$ " - 9 $\frac{1}{2}$ # casing, set @ 3155.72', cemented with 100 sx. of common 10% salt, 10 bbls. salt flush. Job complete at 12:30 a.m., 6/12/81.

SAMPLE TOPS:

Anhydrite: 862'
B/Anhydrite: 900'

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1981

STATE OF KANSAS

COUNTY OF SEDGWICK

CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the JACOB #1, C W/2 E/2 NE, Section 14-13S-15W, Russell County, Kansas.

ABERCROMBIE DRILLING, INC.